

**Public Notice – 401 Certification/Dredged or Fill Waste Discharge Requirements
Application**

Date:

January 3, 2023

Applicant:

Southern California Gas Company
Anthony Gradillas, Project Manager
8101 Rosemead Blvd, Pico Rivera, California 90660
Phone: (310) 995-0301
Email: agradillas@socalgas.com

Duly Authorized Representative:

Southern California Gas Company
Albert Garcia, Director – Environmental Services
555 West 5th Street, Los Angeles, California 90013
Phone: (214) 244-2958
Email: agarcia6@socalgas.com

Project Name:

Shaver Summit Pressure Limiting Station Redesign Project, located in Riverside County, California

WDID No.: 7A333250001, RM 450356, Place ID 884568

Receiving Water:

10 unnamed unvegetated ephemeral dry drainages; no drainage to named waterbody

Location:

City or area: Located north of Interstate 10 (I-10), east of Cottonwood Spring Road, and South of Joshua Tree National Park between the Cottonwood and Orocopia Mountains. The area is approximately 2 miles northwest of Chiriaco Summit, in unincorporated Riverside County, California 92201

Latitude/Longitude:

- 33.6671°N, -115.7594°W (facility expansion area)
- 33.6677°N, -115.7459°W (laydown yard)

Section, Township, Range: Sections 8 and 9, Township 6 South, Range 12 East

Project Description:

The Southern California Gas Company (SoCalGas) is proposing the Shaver Summit Pressure Limiting Station Redesign Project (Project) to modify the existing Shaver Summit Pressure Limiting Station (facility) to meet current standards associated with corrosion and cathodic protection.

The Project involves the installation of two new pressure limiting device stations associated with high pressure natural gas transmission pipelines, excavation and daylighting of existing high pressure gas lines, installation of pipeline crossover sections and mainline valves, installation of new anode wells, removal of release valves, and backfilling of excavated areas and exposed high pressure gas line infrastructure. The Project will require an expansion of the existing facility, approximately 110 feet by 85 feet, and an expanded easement which will be approximately 390 feet by 270 feet following construction activities.

The planned facility expansion will all be carried out within the recently expanded SoCalGas right-of-way (ROW). Expansion will require the rerouting of two ephemeral drainages around the new facility footprint and will permanently redevelop approximately 170 feet of the existing dirt access road. A new security fence will be built around the expanded facility. An approximately 2.8-acre temporary laydown yard and staging area will be constructed about 4,000 feet east of the facility, and will be used for fabrication, materials storage, and equipment storage during construction. Temporarily impacted areas will be restored as necessary.

Anticipated Project Start and End Dates:

June 1, 2023 – October 31, 2023

US Army Corps of Engineers Nationwide Permit Number(s):

n/a

Action:

Pending

Water Board Contact:

Kai Dunn, Supervising Water Resource Control Engineer
(760) 776-8986

Email: kai.dunn@waterboards.ca.gov